



ADDENDUM NO. 1
DPW #12-061-B
IDOC Mechanical Screening Project

Project: DPW 12-061-B: Wastewater Sludge Removal – Mechanical Screening Project
Owner: Idaho Dept. of Admin., Div. of Public Works (DPW), Dept. of Corrections (IDOC)
Date: August 8, 2012
Project No. DPW 12-061-B

To All Bidders:

Bidder's submitting proposals for the above project shall take note of the following changes, additions, deletions, clarifications, etc. in the Contract Documents, which shall become a part of and have precedence over anything contrarily shown or described in the Contract Documents, and all such shall be taken into consideration and be included in the Bidder's Bid Proposal.

Refer to attached sheets:

 8/8/12
Bradley S. Bjerke, P.E. Date

FORSQREN ASSOCIATES INC.

**ADDENDUM NO. 1
DPW #12-061-B
IDOC Mechanical Screening Project**

For Bids Due: Tuesday, August 14, 2012, 2:00 PM (MST)

Revised Bids Due Date: Tuesday, August 21, 2012, 2:00 PM (MST)

ADDENDUM NO. 1

SPECIFICATIONS

AB – ADVERTISEMENT FOR BIDS

1. Change bid date from August 14, 2012 to **August 21, 2012**.
2. No deposit will be required for obtaining the documents in electronic format (pdf format on CD). Printed copies will not be provided by Engineer.
3. Add to paragraph 8, **A second pre-bid conference will be held on Monday, August 13, 2012 at 9 am**. Please meet at the entrance gate (east side) on Pleasant Valley Road at 8:45 am. All interested bidders shall then drive to the parking/check-in area as directed by IDOC staff. Security check-in will then be processing at the security desk at the same time. If not present for this initial check-in, admittance will not be granted.

DRAWINGS

1. Sheet 5, Add sentence to Note 1. Pipe bedding shall adhere to pipe manufacturer's recommendation. Existing surface conditions along pipeline is sage brush. After re-grading to match adjacent grade, no additional surface preparation is required (seeding not required).
2. Sheet 5. Add Note 2. Areas of roadway will be disturbed with widening to the east of the new screen structure. Roadway areas disturbed by construction and widened roadway area shall be constructed using 6-inch base of imported 3-inch uncrushed aggregate per Idaho Standards for Public Works Construction (IDPWC) section 801.2.2 and 4-inch road top consisting of imported crushed aggregate type 1 per Idaho Standards section 802.2.2.
3. Sheet 5. Add Note 3. Two existing grease traps are located on each side of the existing access road north of the construction area. Locate and protect these manholes during construction.
4. Sheet 5, Add Note 4. Please note the slope of the construction area and manage accordingly. Contractor shall follow construction protocol for stormwater control, disturbance area less than one acre.

END OF ADDENDUM